
RIDGE SPRING-MONETTA K-12 CAMPUS PHASE ONE - NEW CLASSROOM WING

Aiken County Public Schools



CONSTRUCTION DOCUMENT SUBMITTAL

October 9, 2012

Aiken County Public Schools October 9, 2012

Page 1 of 14

TABLE OF CONTENTS

- PROJECT DESCRIPTION
- PROJECT PROGRAM
- MASTER PLANS
- PHASE ONE DRAWINGS
- STATEMENT OF PROBABLE COST
- PROJECT SCHEDULE




Existing RSM High School

Aiken County Public Schools October 9, 2012

Page 2 of 14

PROJECT DESCRIPTION:

The existing Ridge Spring - Monetta (9 thru 12) High School site has a 15 to 20 year Master Plan to be redevelopment into a K - 12 facility. Phase One of the master plan is a New Classroom Building that will temporarily house the 6th, 7th, and 8th grade students. As the development of the site moves forward, the phase one classroom wing will be converted into high school space.



RSM K-12 Master Plan

Phase One Site Improvements will include a new bus/service drive, new middle school visitor/staff drive and parking, utilities, and a new turn lane on Trojan Road. All improvements have been planned to support the future phases of the master plan.

The new 34,875 square foot building will house 7 general classrooms, 2 science labs with a shared prep room, 3 computer labs, adequate administrative support spaces, a kitchen/cafeteria and building support.

<u>General Construction</u>: The building structure consists of load bearing masonry walls with brick veneer on the exterior and aluminum windows with integral blinds. The roof will be an ACPS Standard, Energy Star Rated, Built-Up Roof system over metal decking and steel joist structure.

<u>Mechanical System:</u> The new HVAC system shall consist of indoor air handling units. The systems serving the classroom areas shall be VAV with electric heat in the VAV boxes. The systems serving the Kitchen and Cafeteria shall be constant volume with electric heat in the air handling units. Cooling for the new system shall be provided by two air cooled chillers with a primary/secondary chilled water piping system that distributes the chilled water to the required locations.

<u>Electrical System:</u> The new electrical service to this building will be a 3 phase, 4 wire service coordinated with the local power company. An addressable fire alarm system will be installed in this facility. All work shall comply with local codes, the National Electrical Code and other applicable N.F.P.A. Standards, and requirements of the IBC as well as the OSF Design Guidelines.

<u>Plumbing System:</u> All water piping shall be copper pipe with soldered fittings. All new toilet groups are to be provided using flush valve fixtures. A new electric water heating system will be provided for group toilets with recirculation pumps to maintain desired water temperature. A new electric water heating system will be provided with storage tank and recirculation pumps to support the kitchen. The grease laden waste from the kitchen will flow thru a certified grease interceptor prior to discharge into the sanitary system. All kitchen fixtures provided for the kitchen will be stainless steel.

Submittals and State Reviews:

Construction documents have been completed and submitted to OSF for final approval. Final Approval will be contingent upon receiving letters of acceptance from SCDOT and SCDHEC.

<u>SCDOT</u> had some concerns about additional traffic that would be generated by adding the middle school program to the site. The several meetings and discussion took place to review the scope and potential cost. SCDOT agreed to require minimal road improves to lessen the cost impact on Phase One, however it was noted that phase two would require significant road work to handle the additional cars for kindergarten. **SCDOT acceptance was received on September 20, 2012**

<u>SCDHEC</u> acceptance is pending their review of the documents. Documents have been held in review since July pending acceptance of the on-site sewer by the local waste water manager. The proposed location of the septic drain field was not acceptable and new locations were investigated on two separate occasions. The new location was accepted on August 30th and the Civil engineer has developed the septic system design based on the new location. **SCDHEC kitchen equipment plan review is still incomplete.**

DESIGN DEVELOPMENT




6th, 7th, & 8th Grades


RSM - Phase One Program New Middle School Classroom Building


200 Students 16 Teachers and Staff


Space Name	#	Area	Total	Area	Comments
GENERAL CLASSROOMS (Home Rooms)					
Grades 6-8	6	820	4,920		
Flex Classroom	1	840	840		math, language arts, social studies
Subtotal	7		5,760		
RESOURCE/SUPPORT CLASSROOMS					
Resource Room	2	308	616		(Guidance / Spec. Ed. / Reading Inter. / Etc.)
I.S.S.	1	412	412		
Self-Contained Classrooms	2	802	1,604		
Self-Contained Toilet & Storage	1	400	400		
Science Labs	2	1,010	2,020		
Prep Room	1	329	329		
Subtotal			5,381		
TECHNOLOGY					
Accommodations Lab	1	720	720		15 netbook computers
Synergistics Lab (Math/Science)	1	1,067	1,067		includes sink and storage
Computer Lab	1	720	720		Keyboarding / Computer Apps
Subtotal			2,507		
ARTS EDUCATION		Shared	with High S	chool	
MEDIA CENTER		Shared	with High S	chool	Each middle school classroom has its own in- class library. Research will occur in the existin
PHYSICAL EDUCATION		Shared	with High S	chool	
ADMINISTRATION					
Entry /Waiting	1	270	270		
Reception	1	332	332		
Principal Office	1	130	130		
Staff Offices	2	130	260		
Small Conference Rooms	1	227	227		
Record Storage / Vault	1	60	60		
Admin Workroom	1	325	325		
Teacher Workroom	2	139	278		
Staff Toilets	4	52	208		
Health Room w/ Toilet Book Storage	1 1	282 126	282 126		
Subtotal	- 1	120	2,498		
FOOD SERVICE					
Kitchen/Serving	1	3,500	3,500		
Dining	1	4,346	4,346		
Chair Storage	1	120	120		
A/V Equipment Storage	1	40	40		
Subtotal			8,006		
PLANT OPERATIONS					
Janitor/Laundry /Storage	1	150	150		
Group Toilets	1	534	534		
General Storage Subtotal	1	100	100 784		
			, , , ,	04.004	
BUILDING NET AREA	ISS DO	rcentage	39.9%	24,936	
		0	37.7%		
Gross Area (Circu., Mech, Elect, Equip, Wall	ls, Etc	.)		9,939	
BUILDING TOTAL AREA				34,875	
SITE PROGRAM SPACES					
			68	Spaces	
SITE PROGRAM SPACES Car Parking (Visitors and Staff)				Spaces	required # of parkings spaces will vary pendi County review
				Spaces	


Page 5 of 14


















PHASE ONE - FLOOR PLAN





BUILDING ELEVATIONS

architectur

K

PROJECT No: 1120 OCTOBER 9, 2012

RIDGE SPRING-MONETTA K thru 12 CAMPUS





AIKEN COUNTY PUBLIC SCHOOL DISTRICT RIDGE SPRING-MONETTA K THRU 12 CAMPUS Statement of Probable Cost

Phase One - Construction Documents

	Flidse Olle - CO		115					
SITEWORK				Total Project				
SHEWORK		Earthwork	¢145 741					
		Site Improvements	\$145,741 \$520,735					
		Site Improvements Site Utilities	\$520,735 \$504,300					
		Site Otimies	\$304,300					
	Sub-Total	\$33.57 s	f	\$1,170,776				
BUILDING		34,875 s	f					
DOILDING		\$ / SF	•					
	General Conditions	\$20.93	\$730,103					
	Gen. Construction	\$84.92	\$2,961,702					
	Plumbing	\$14.94	\$520,974					
	Fire Protection System	\$3.25	\$113,211					
	Mechanical	\$33.38	\$1,164,081					
	Electrical	\$31.11	\$1,084,800					
		\$188.53						
	Sub-Total		\$6,574,871					
BUILDING A	ND SITE	\$222.10 s	f	\$7,745,647				
	Contingency: (Building and Site)	5.0%	\$387,282					
	Escalation	1.5%	\$116,185					
	Allowances (soils & misc steel)		\$75,000					
	Allowances (Fire Alarm, Telecom, Security, Sound) \$110,000							
CONSTRUCT	TION SUB-TOTAL			\$8,434,114				
NON - CONS	TRUCTION							
	Soft Cost		\$1,300,000					
	(Design Fees, Inspections, Surveying,		ψ1,000,000					
PROJECT T	OTAL (excluding Alternates)			\$9,734,114				
PROJECT BL	IDGET			\$7,775,000				
				$\varphi_{-}, = 0, 000$				

-25.2% Over Budget (\$1,

(\$1,959,114)


RIDGE SPRING / MONETTA - NEW CLASSROOM BUILDING

PROJECT SCHEDULE

- 1		e
-74	e i	-
	R	∍
10.0		+
		U
	e	e
	_	+
	in	-
	Ч	U
		<u> </u>
	А	

	_											-					
	MAY														МАҮ		
2014	APR												оссиру		APR		
	MAR														MAR	2014	
	FEB							Substantial Completion			l				FEB		
	JAN							Substantial							NAL		
	DEC						L								DEC		
	VON										l				VON	_	
	OCT										l				ост		
	SEP										(16 MONTHS)				SEP	_	
	AUG										CONSTRUCTION (1				AUG		
3	JUL										CONST				JUL	3	
2013	NNr										l				NNr	2013	
	MAY										l				МАҮ		
	APR						on Start				l				APR		
	MAR						Bid Award / Construction Start				l				MAR		
	FEB			1	_	-	Bid Award				l				FEB		
	JAN		OSF - Final Approval		Receive Bids										JAN		
	DEC		OSF - Fina						VARD						DEC		





Page 14 of 14